

268788 **2395 Julie Way, DeWitt, MI 48820** **\$454,900**
Residential Active



Front Elevation

County: Clinton
City: DeWitt
Key: NONE
Township/Tax Authority: DeWitt Charter Twp
Property Sub-Type: Single Family Residence
Senior Community: No
List Price: \$454,900
Baths Full - Total: 2
Baths Half - Total: 1
Baths - Total: 3
Bedrooms Total: 4
Directions: S DeWitt Rd./ Brookview lane - Head W on Brookview lane, N on Wilson to Julie Way
Legal: LOT 88 CREEPING BROOK ESTATES NO. 7, SEC 5, T5N2R2W. FROM 050-005-100-045-51 FOR 2004 ROLL.

Lot Acres: 0.25
Lot Size Dimensions: 85X128
School District: DeWitt
Subdivision: Creeping Brook
Home Warranty: Yes
Reserved Items: No
Year Built: 2023
Occupancy: At Close
Building Area Total SqFt: 3,168
Total Livable Area: 2,348
Association Fee/Yr:

2395 Julie Way

Parcel #: 050-175-000-088-00	Tax Year: 21	Taxes: \$719.98
State Eq Value: \$22,700	Taxable Value: \$22,700	Zoning: Residential
#Full Baths 3: 0	#Half Baths 3: 0	Level 1 Finished Area: 1,162
#Full Baths 2: 2	#Half Baths 2: 0	Level 2 Finished Area: 1,186
#Full Baths 1: 0	#Half Baths 1: 1	Level 3 Finished Area: 0
#Full Baths B: 0	#Half Baths B: 0	Below Grade Finished Area: 0
		Above Grade Finished Area: 2,348
		SqFt - Basement: 820

Room Name	Level	Dimensions	Room Features	Remarks	Room Name	Level	Dimensions	Room Features	Remarks
Primary Bedroom	Second	13.8 x 14.6	Carpet Floor		Bedroom 2	Second	12.4 x 12.2	Carpet Floor	
Living Room	First	14 x 12	Carpet Floor		Bedroom 3	Second	11.4 x 11.4	Carpet Floor	
Dining Room	First	12 x 11		Luxury Vinyl Floors	Bedroom 4	Second	13.8 x 11.4	Carpet Floor	
					Kitchen	First	9.1 x 13.4		Luxury Vinyl Flooring
					Office	First	13.8 x 10		Study
					Other	First	11.6 x 11		Sunroom

Association Amenities: Maintenance Grounds
Appliances: Dishwasher; Microwave; Stainless Steel Appliance(s)
Basement: Concrete; Daylight; Egress Windows; Full; Sump Pump; Walk-Out Access
Community Features: Curbs; Sidewalks; Street Lights
Current Financing: None
Cooling: Central Air
DPR: DPR Eligible: Yes
Exterior Features: Lighting; Rain Gutters; Storage
Electric: 200+ Amp Service
Exterior: Vinyl Siding
Flooring: Carpet; Vinyl; Other; See Remarks
Fencing: None
Foundation Details: Concrete Perimeter
Fireplace Features: None
Heating: Forced Air; Natural Gas
Interior Features: Entrance Foyer; High Ceilings; Kitchen Island; Pantry; Stone Counters; Storage; Walk-In Closet(s)

Land & Acreage: Up to 1/4 Acre
Lot Features: City Lot; Few Trees; Front Yard; Gentle Sloping; Level; Rectangular Lot
Laundry Features: Electric Dryer Hookup; Laundry Room; Main Level; Washer Hookup
Levels: Two
Property Conditions: Proposed Build
Parking Features: Garage Spaces: 2; Attached; Concrete; Driveway; Garage Door Opener; Garage Faces Front; See Remarks
Patio & Porch Features: Deck; Porch
Pool Features: None
Property Use: Primary
Roof: Shingle
Road Surface Type: Asphalt
Sewer: Public Sewer
Terms: Cash; Conventional
View: Creek/Stream; Neighborhood; Trees/Woods
Window Features: Low Emissivity Windows
Water Source: Public

Public Remarks: Welcome Home! This 2348 Finished Two-Story floor-plan offers the option of a finished lower level including a 5th bedroom, full bath & recreational room adding a proposed 820 sq. ft. This mature subdivision offers a walkout and daylight basement windows to enjoy the backyard tree line view with close proximity to downtown DeWitt & walking distance to David Scott Elementary School.

Buyer Agency Fee: 3%


James Giguere
 Giguere Realty & Development, L.L.C.
 6200 Pine Hollow Dr., Ste 100
 East Lansing, MI 48823
 517-204-0818
jim@giguerehomes.com


Information is deemed to be reliable, but is not guaranteed. © 2024 MLS and FBS. Prepared by James Giguere on Monday, February 26, 2024 6:01 PM. The information on this sheet has been made available by the MLS and may not be the listing of the provider.



Front Elevation

SCALE 1/4" = 1'-0"





FIRST FLOOR - 1,162 S.F.
 SECOND FLOOR - 1,186 S.F.
 HOUSE TOTAL - 2,348 S.F.
 GARAGE 506. SQ. FT.

COPYRIGHT © 2022
 FIGUERE HOMES
 ALL RIGHTS RESERVED

NOTES:
 ALL DIMENSIONS ARE
 DOES NOT INCLUDE SHE
 STANDARD 1ST FL WA
 OTHER WISE NOTED. AL,
 SECOND FLOOR WALLS
 AT 7'-0 7/8" AFF.
 ALL WINDOWS ARE JE
 EQUALS UNIT SIZE IN
 INTERIOR DOOR ROUGH
 NOMINAL WIDTH + 2"
 NOMINAL HEIGHT + 2"
 CALL OUT OPENING SI
 PROVIDE AND INSTALL
 AND DRAFTSTOPPING A
 EFFECTIVE BARRIER B
 INSTALL 7/16" OSB
 DECK MATERIALS TO
 FASTNERS. INSTALL FL
 ALL SILL PLATES TO
 APPROVED FASTNERS.
 PROVIDE 2X10 BLOCK
 WINDOW FOR INTERIOR
 EXTERIOR FOR SHUTTE



SPECIFICATION SHEET

Columbus II Plan

Date: Sept 25th, 2022

Buyer:

Lot: 88 **Subdivision:** Creeping Brooks Estates Plan #2

Basement: Walk Out / Optional Finish

1) Foundation: 8' x 8" poured concrete wall except 8' x 10" in brick area or per print. 8' x 8" garage frost walls or per print. Weep tile covered with pea stone inside and outside footings to sump crock or gravity feed line or walkout basement. 4" bleeder tile under basement window(s) to footing drains. Damp proofing to code. **(1) Egress Window (1) Sliding Patio Door (1) Bathroom Window**

2) Framework: 9' first floor ceiling height with **8'** second floor ceiling height.

Wood basement beams and steel columns by builder.

First floor deck: **L.P.I. floor** joists per print or code - whichever is greater.

Sub floor: 3/4" T&G OSB glued nailed and screwed.

Exterior walls: 2x4 studs, or per print, 16" o.c., 7/16" OSB sheathing

Interior walls: 2x4 studs, 16" o.c. or per print. All frame lumber #2 or better.

Roof framing: Engineered trusses 24" o.c., or rafters per code, 1/2" OSB roof sheathing with clips on trusses and 1/2" OSB with clips on rafters.

Roofing: **CertainTeed Landmark Dimensional** shingles with Ice & water shield rolled roofing for valley base and 15lb felt underlayment. Attic ventilation by ridge vents and soffit vents.

Installation of pre-finished gutters and down spouts as required for proper drainage.

Entire building wrapped in PermaPro or equivalent house wrap, per code.

Additional Item: Option for Lower Level Finish

3) Insulation: Energy seal package included

Wall cavity: **R-13 fiberglass batts** or equal.

Attic: **Blown Cellulose insulation** equal to R-38 factor.

Garage: Insulate house/garage wall. No insulation on garage sidewalls, front wall or ceiling.

Bond: **R-19 Fiberglass batt insulation.**

Cantilever spaces: **R-30 Fiberglass batt Insulation**

All window and exterior door jambs filled with foam insulation. All exterior duct and pipe openings sealed with caulk or equal.

Unfinished Basement R-13 fiberglass insulation between 2x4 walls set 24" OC.

All window and exterior door jambs packed with fiberglass insulation. All exterior duct and pipe openings sealed with caulk or equal.

4) Exterior: Vinyl Siding /Brick per elevation

Siding: **Ply Gem standard selections**

Creeping Brooks Estates Lot #88

Specifications

9/25/2022

Page 1 of 6

Exterior trim: Painted LP smart trim on front elevation. All other corners and trim to be vinyl, per plan.

Fascia: Aluminum (Color: per selections)

Soffit: Vented aluminum (Color: per selections)

5) Windows: Jeld-Wen single hung windows and sliding glass doors **Low-E** glass type and size as per blueprint. Color: White Grills: between the glass per elevation.

Site built MDF window jambs

6) Masonry: Brick veneer per elevation & selections sheet per print. Brick allowance 600/1000.

7) Fireplace: None

8) Doors:

Front door system: Fiberglass 6-panel insulated smooth skin with 15" transom.

Fire door: Insulated fiberglass, 6-panel, 20-min rated, per plan

Interior doors: Hollow core, 6-panel, smooth.

Garage doors: C.H.I. Series# **22/4250**, 16' x 7', embossed steel, non-insulated, raised panel, 1/2 hp. Liftmaster operator model #**8365** with integrated photocell safety sensor, two hand control(s).

Additional Item: Double 2-6 hollow core 6-panel doors at Study

Additional Item: Option for Lower Level Finish

9) Hardware: Kwikset Satin Nickel

Kwikset "Chelsea" series 801CE LIP Satin Nickel grip handle on main exterior entry.

Kwikset B360 series dead bolts on all exterior doors (except sliding glass doors).

Hancock round design Satin Nickel 740H F series keyed locks on exterior doors (except main entry and sliding glass doors and French doors as applicable).

Hancock round design Satin Nickel 730H/720H series on interior doors (privacy sets at baths and bedrooms, passage sets elsewhere).

Bi-fold knob per standard selection. Doorstops installed on all active doors.

Bath Hardware: Taymor Maxwell- Chrome Towel bar: (1) per full bath, Toilet paper holder: (1) per bath, Towel Ring: (1) per bath

10) Plumbing: Supply Lines: PEX; Waste Lines: P.V.C.

Owners Bath: Color: **White**; Finish: **Chrome**

Shower: Walk in Shower Tile to 7'-0" height *Option: Fiberglass SHLS-60 with glass slider*

Shower Valve: Delta "Woodhurst" **T14232/R10000**

Shower Rod: Standard chrome

Lavatory: **Cultured Marble** w/ Integrated sinks (2)

Lavatory Faucet: **Delta** "Woodhurst" **2532LF-MPU** (2)

Toilet: **Gerber SE-20-102** round w/ seat

Bath #2: Color: **White**; Finish: **Chrome**

Tub/Shower: Aker **CM-60** Fiberglass

Shower Rod: Standard chrome

Creeping Brooks Estates Lot #88

Specifications

9/25/2022

Page 2 of 6

Tub/Shower Valve: **Delta** "Woodhurst" **T14432/R10000**
Lavatory: **Cultured Marble** w/ Integrated sink (2)
Lavatory Faucet: **Delta** "Windemere" **B2596LF (2)**
Toilet: **Gerber SE-20-102** round w/ seat

Powder Room: Color: **White**; Finish: **Chrome**

Pedestal: **Mansfield Barrett 330**
Lavatory Faucet: **Delta** "Woodhurst" **2532LF-MPU**
Toilet: **Gerber SE-20-102** round w/ seat

Optional L.L. Bath #3: Color: **White**; Finish: **Chrome**

Tub/Shower: Aker **CM-60** Fiberglass
Shower Rod: Standard chrome
Tub/Shower Valve: **Delta** "Woodhurst" **T14432/R10000**
Lavatory: **Cultured Marble** w/ Integrated sink (1)
Lavatory Faucet: **Delta** "Windemere" **B2596LF (1)**
Toilet: **Gerber SE-20-102** round w/ seat

Kitchen: Sink: **Undermount Stainless Steel Double Bowl**

Faucet: **Delta** "Foundations" **B4310LF-** Chrome
Disposal: Badger ½ horsepower
Ice maker line included.
Dishwasher hookup included

Laundry: Washer plumbing for future hookup included

Floor drain w chrome finish included
Dryer exhaust vented to exterior

Basement and Miscellaneous:

One 50-gallon power direct vent natural gas hot water heater
Number of outside lawn faucets: **2**
Rough in three-piece bath in Lower Level
Humidifier connection
Submersible sump pump with cover.

*If colored baths are included, the color must be selected before framing and will cause an additional charge to the contract price.

11) Electrical: Service: 150-amp circuit breaker: underground.

Standard switches: color **White** and **standard Plugs.** Color: **White** standard

All openings governed by the prevailing electric code. All wiring, outlets, and switches are to be shown on electrical floor plan including **0** phone jacks, **3** cable TV outlets, **2** weatherproof exterior electrical outlets and recessed lights per plan. Basement lights in unfinished areas to be porcelain

switched together.

Range: **Electric**

Dryer: **Electric**

Additional Item: Option for Lower Level Finish

12) Light Fixtures: Allowance provided below. Light fixture allowance includes all fixtures, light bulbs, doorbell, ceiling fans, under cabinet lights, step lights, and accessories, as shown on plans. Late installation due to back-ordered fixtures, Buyer changes during final installation, or additional labor required for intricate fixtures may result in an extra labor charge not included in bid.

13) Mirrors: Plate Glass Mirrors sized to be 3” less than the width of the countertop and 42” high. Oval mirror to be installed above pedestal in Half Bath.

14) Heating: Carrier 95% plus efficient forced air furnace with electronic ignition. Registers in floor. Outside air intake into plenum. Furnace fueled by natural gas. Outside venting for dryer and baths included. Heating design to be governed by the prevailing mechanical code. Equipment and register locations to be determined and guaranteed by the heating contractor.

Central air conditioner..... Yes

Humidifier Yes, with auto adjust humidistat

Thermostat type Digital programmable

Special gas lines HWH, furnace

Venting (4) Bath fans, (1) Dual speed bath fan, (1) Micro hood, (1) Dryer

Additional Item: Option for Lower Level Finish

15) Drywall: The project will be ½” drywall with all joints filled and taped. Knock down ceilings throughout the project.

Garage: Drywall only.

Additional Item: Option for Lower Level Finish

16) Exterior Concrete: All concrete to be approximately 4" thick. Basement to be troweled smooth, garage semi smooth, all exterior concrete to be broom finished with expansion and control joints to best control cracks. Shrinkage cracks are common and should be expected. Basement floor per print. Garage floor per print with minimum 2" slope to overhead door(s).

Drive.....16’ wide concrete, per site plan

Approach..... 16’ wide concrete with 2’ flares.

Lead walk..... 3.5’ wide concrete, per site plan

Steps.....1-step width of entry door

City Sidewalk..... Use existing sidewalk, replace as needed.

17) Deck: 12’x12’ pressure treated lumber with pressure treated railing and 2”x2” square balusters. No steps to grade

18) Finished Flooring:

Carpeting: Group #1 w/ 8# pad; Great Room, Study, Main stairs, Second floor hallway, Owners Bedroom, Bedroom #2, Bedroom #3, Bedroom #4, Option for Bedroom #5, including Bedroom closets.

Creeping Brooks Estates Lot #88

Specifications

9/25/2022

Page 4 of 6

LVT: Group#1 Standard selections; Foyer, Main Floor Hallway, Mud Room, Laundry Room Dining Room, Kitchen, Sunroom, Owners Bath, Bath#2, Option for L.L. Bath#3 and Powder Room

19) Cabinets: HomeCrest

Group #1 standard selections; Kitchen, Owners Bath, Bath #2, and Option for L.L. Bath #3

Crown molding: Standard selection included on Kitchen cabinets

Soft close doors and drawers: Included on all cabinets

Cabinet Hardware: Builders Choice, Included on all cabinets

Note: medicine cabinets are not included. Layout of cabinets and vanities are figured per the Builder's print. If the cabinet plan or selection should be changed from the Builder's print, there may be an additional cost (or credit) to Buyer for labor and materials to install the revised layout.

20) Interior Trim

Trim: #473 3 1/4" base, #433 2 1/4" casing "Craftsman Style" ultralite MDF paint grade

Base shoe applied to all hard floor areas.

Windows: MDF window jambs

Garage: No finish trim

Closets: White open slide wire shelving, per plan.

Basement staircase: Finished with drywall, paint and handrail. **No carpet**

Main staircase: 41" high 1/2 wall with painted MDF cap, per plan main floor and 2nd floor.

Additional Item: Option for Lower Level Finish

21) Counter Tops:

Quartz promo standard selections; Kitchen and Island with 10" overhang

Cultured Marble: Group #1 standard selections; Owners Bath, Bath #2, and Option for L.L. Bath #3.

Layout of counter tops are figured per Builder's print. If the layout of counter tops changes from Builder's print, there may be an additional cost to Buyer for additional countertop material and installation of the revised layout, back splashes, etc...

22) Appliances: GE Stainless Steel

Micro hood: **JVM3160RFSS** or equal

Dishwasher: **GDF530PSMSS** or equal

Appliances purchased from sources other than through the Builder must be installed by the supplier after closing. Builder will only install appliances ordered through the Builder. **Buyer must purchase built-in and vented appliances through Builder.** There will be an extra charge for non-conventional appliances such as built-in refrigerators, pop up cook top vents, panel doors on appliances, trim kits for appliances, etc... Availability of appliances during final installation is the responsibility of Buyer unless it is ordered through the Builder. Any late installation due to back orders or Buyer changes may result in an extra charge not included in bid. The installation charge for each appliance ordered through Giguere Homes is included in the appliance package order through the

Creeping Brooks Estates Lot #88

Specifications

9/25/2022

Page 5 of 6

builder.

23) Painting: Interior walls: Finish paint all finished drywall walls except wallpapered areas unless otherwise specified. Painted ceilings are not included and are an extra charge item. Interior painting includes one coat of **O'Leary Paint's** flat latex primer and one coat of **O'Leary Paint's Ceramic** latex paint or equal in closets, color: Pearl White. Coverage of paint may vary depending on the color chosen. Sizing of walls for wallpaper is not included.

Interior trim: All exposed wood to be painted 2-6-1 Pearl White. Latex, satin finish painted wood to have one coat primer, and one coat finish. Painted wood will be caulked. Shrinkage cracks in caulk are common, should be expected, and are considered a homeowner maintenance item.

(1) paint color thru-out home are included. Additional colors are \$200.00.

Stained wood to have one coat O'Leary Finishing or equal as determined by Builder, one coat sanding sealer, and one coat varnish.

Garage: No paint

Exterior: One coat of paint, except pressure treated lumber (and other maintenance free materials such as vinyl and aluminum), and caulk around windows and doors.

Exterior Decking: (if included in contract) will not be painted or stained unless mutually agreed otherwise.

24) Grading: Backfilling will be sufficient to provide access for construction and grading to provide drainage away from the building. Any disturbed area that can be graded with a bulldozer on the building site within **30 feet** of building shall be rough graded at time of backfill and blade graded at completion. Builder is not responsible for settling around the house, trenches and so forth, after the building is occupied. Builder NOT responsible for any existing tree dying except those planted and guaranteed by Landscape Company. **No Landscaping.**

25) Extras: Any additions, extras, or changes made by buyer shall be on a CHANGE ORDER form and signed by both Builder and Buyer. Change order payments are due at the time of signature.

26) Selection Schedule: It shall be the obligation of Buyer to supply Builder with a signed copy of the selection schedule in a timely manner after signing the construction contract. Construction of home will not begin until all selection with final plan details are signed off by homeowner.

27) Utilities: Temporary power and utilities (electricity, natural gas, propane, water, etc...) will be placed in Builder's name during construction. The following costs are the Builder's responsibility. Utility hookups include public water, public sewer, storm sewer, underground electric and underground gas.

28) Plans: Cost of plan development included. If the Buyer requests custom changes, then the Buyer shall pay for design services. (See Design Agreement form).

29) Financing: Cost for construction financing is **not** included.

30) Allowances:

All allowances included. The allowance dollar amounts set on the specified items in this agreement are hereby agreed upon by both Buyer and Builder. The allowances are amounts which can be spent by Buyer for those selected items as denoted in these specifications. An allowance is set when Builder is unable to determine the exact cost of any product. An allowance item may cost less or more than specified sum. If it is less, Builder will refund the difference to Buyer.

31) Miscellaneous items/ Comments:

Vinyl mailbox with pressure treated post
Interior cleanup of construction debris included.
Exterior cleanup and haul away of construction debris include

32) Special Allowance Summary:

Light Fixtures.....	Allowance \$2,000.00
Appliances.....	Allowance \$800.00